

SCHEDULE –A

Providing Engineering and Technical Maintenance Services at Kurnool Airport

Sl. No	Quantity	Description of work	Specification No/ APDSS/BIS	Unit in figures	Rate	Amount in Rs
1.	1600	Painting road surface marking with adequate no's of coats to give uniform finish with ready mixed road marking paint conforming to IS : 164, on bituminous surface in white/yellow shade, including cleaning the surface of all dirt, scales, oil, grease and foreign material etc. complete runway painting	APDSS	1 Sqm	161	257600
2.	10	Repairing and refixing of doors / windows shutters including removal of shutter from chowkhat, cutting wherever necessary, removing and refixing butt hinges on either side of frame of shutter wherever required. Door/window	APDSS	each	509.08	5091
3.	25	Providing and fixing 1mm thick laminate (Decolumn or equivalent) including finishing etc. as per direction of Engineer-in-charge.	APDSS	1 Sqm	1369.67	34242
4.	30	Providing and fixing aluminium sheet of required gauge on doors, gutters, etc. with steel screws etc., complete.	APDSS	1 Sqm	1095.99	32880
5.	1000	Tightening of barbed wire or G.I. wire fencing including fixing of broken hooks complete.	APDSS	Rm	5.34	5340
6.	100.00	Cleaning of choked / blocked Rain water pipe / soil waste and vent pipes.	APDSS	Rm	18.86	1886
7.	24	Cleaning of choked / blocked Manhole including connected sewerage pipes up to the next manhole either manually or using sewer rod	APDSS	No	725.39	17409
8.	10	Cleaning of choked / blocked Gully traps including connected soil waste / sewerage pipe up to the nearest manhole.	APDSS	No	168.81	1688
9.	25	Cleaning of choked / blocked EWC / IWC including connected traps and soil waste pipe up to the nearest opening point in the soil waste pipe.	APDSS	No	168.81	4220
10.	30	Cleaning of choked / blocked Wash basin / kitchen sink including connected traps.	APDSS	No	42.20	1266
11.	200.00	Cleaning of choked / blocked House drain	APDSS	Rm	9.30	1860
12.	1000.00	Cleaning of choked / blocked Storm water drain (road side)	APDSS	Rm	31.22	31220
13.	5000	Cleaning of choked / blocked Strom water drain up to 1Mtr width and Depth up to	APDSS	Rm	71.98	359900

		1.5Mtr				
14.	10	Cleaning of choked / blocked Box Culvert up to 1Mtr width and Depth up to 1.5Mtr	APDSS	No	99.67	997
15.	0	Cleaning of choked / blocked Septic tank (Surface area up to 7.5 sqm)	APDSS	No	6718.89	0
16.	1	Cleaning of choked / blocked Septic tank (Surface area 7.5 sqm to 15.00 sqm)	APDSS	No	11707.14	11707
17.	0	Cleaning of choked / blocked Septic tank (Surface area above 15.00 sqm)	APDSS	No	14889.67	0
18.	4	Cleaning of underground water tanks / surface water tanks and removing of malba& as directed by Engineer in charger including disinfecting the tank with bleaching powder. Up to 5000 liter capacity (once in 3 months)	APDSS	No	1345.44	1345
19.	580	Cleaning of underground water tanks / surface water tanks and removing of malba& as directed by Engineer in charger including disinfecting the tank with bleaching powder. For every additional 1000 liters capacity.	APDSS	No	266.28	154442
20.	0	Cleaning of GI / MS / Masonry / Sintexover head water tanks including removal of malba as directed by Engineer in charge and disinfecting the tank with bleaching powder. Up to 500 liters capacity	APDSS	No	215.95	0
21.	0	Cleaning of GI / MS / Masonry / Sintexover head water tanks including removal of malba as directed by Engineer in charge and disinfecting the tank with bleaching powder. for every additional 100 liter capacity	APDSS	No	27.70	0
22.	36	Cleaning of GI / MS / Masonry / Sintexover head water tanks including removal of malba as directed by Engineer in charge and disinfecting the tank with bleaching powder. Beyond 10000 liter capacity (once in 3 months)	APDSS	No	6427.35	231385
23.	72	Attending various day to day complaints and rectifying the defects / cause of complaints by deploying labour (unskilled as and when required) with necessary T & P but without changing / replacing the fittings / fixtures. However, the minor stores like screws for tightening hinges, tower bolts, door handles ,minor repair works like rectifying defects in floor springs ,alignment of all types of doors etc., is included in the rate. Per month.	APDSS	Month	15679	112888
24.	24	Attending various day to day complaints and rectifying the defects / cause of complaints by deploying labour (semi – skilled (electrical) as and when required) with necessary T & P but without changing	APDSS	Month	17042	409008

		/ replacing the fittings / fixtures. However, the minor stores like screws for tightening hinges, tower bolts, door handles ,minor repair works like rectifying defects in floor springs, alignment of all types of doors etc., is included in the rate. Per month .electrical works and systems(2)				
25.	72	Attending various day to day complaints and rectifying the defects / cause of complaints by deploying labour (skilled as and when required) with necessary T & P but without changing / replacing the fittings / fixtures. However, the minor stores like screws for tightening hinges, tower bolts, door handles ,minor repair works like rectifying defects in floor springs ,alignment of all types of doors etc., is included in the rate. Per month. Electrical (2) Civil(2) Communication & systems(2) (it & electronics(1),communication systems(1)).	APDSS	Month	18746	1349712
26.	36	Attending various day to day complaints and rectifying the defects / cause of complaints by deploying labour (Supervisors(Civil Engineer-1no, Electrical Engineer-1no, Electronics/IT Engineer-1no) with Diploma qualification as and when required) with necessary T & P but without changing / replacing the fittings / fixtures. However, the minor stores like screws for tightening hinges, tower bolts, door handles ,minor repair works like rectifying defects in floor springs ,alignment of all types of doors etc., is included in the rate.	APDSS	Month	28972	1042992
27.	12	Attending various day to day complaints and rectifying the defects / cause of complaints by deploying labour (Electronics & Communication Engineer-1no with BE/BTECH qualification as and when required) with necessary T & P but without changing / replacing the fittings / fixtures. However, the minor stores like screws for tightening hinges, tower bolts, door handles ,minor repair works like rectifying defects in floor springs ,alignment of all types of doors etc., is included in the rate. d) Per month.	APDSS	Month	37493	449916
28.	5	Providing and fixing PVC 110mm dia P-Trap of approved make complete as per	APDSS	No	701.87	3509

		direction of Engineer-in-Charge.				
29.	1000	Providing and fixing fencing with G.I. barbed wire 15.00 kg /100m (min.) fixed with G.I staples or with G.I. binding wire complete (Length of individual G.I.wire will be measured)	APDSS	Rm	11.48	11480
30.	20	Providing and fixing C.P pillar cock of approved make Jaguar of model No. CQT-CHR-23021 complete in all respects as per direction of Engineer-in-charge. a) 15 mm nominal bore	APDSS	No	2086.12	41722
31.	25	Providing and fixing CP bottle trap for wash basin 32mm dia of approved make (Jaguar) complete in all respects as per direction of Engineer-in-charge.	APDSS	No	1817.79	45445
32.	5	Providing and fixing 8mm thick float glass tinted (Asahi float or equivalent) sheet paneling / glazing with U shaped neosrenemoulded rubber all along the glass edges and complete in all respects as per direction of Engineer-in- charge.	APDSS	Sqm	1788.45	8942
33.	10	Supplying and fixing vertical venetian blinds of gokul, marvel or approved make of 100mm wide including all fittings etc required and complete in all respects as per direction of Engineer-in-charge.	APDSS	Sqm	2190.68	21907
34.	0	Providing and fixing mosquito proof netlon or equivalent over frames of windows, ventilators etc., and fixing arrangement like strapping well crow strip over wooden frames including stitching etc. complete.	APDSS	Sqm	310.84	0
35.	0	Providing and fixing mosquito proof netlon or equivalent over frames of doors etc., fixing arrangement like PVC beading over wooden frames using hinges including fixing charges etc. complete.	APDSS	Sqm	373.01	0
36.	Hour	Providing and operating the tractor dozer for leveling, cutting etc., including transportation to and from the site of operation , fuel charges, driver charge and any other incidental expenses on this account all etc. as directed by the Engineer-in-charge. (The payment will be based on the number of hours worked at the site) 80	APDSS	Hour	1184.15	94732
37.	10	Providing and operating the tractor compressor drill machine. Including transportation to and from the site of operation, fuel charges, driver charge and any other incidental expenses on this account all etc. as directed by the Engineer-in-charge.	APDSS	day	9473.23	94732
38.	80	Providing and operating the J.C.B. for leveling, cutting etc., including	APDSS	Hour	1657.82	132626

		transportation to and from the site of operation, fuel charges, driver charges and any other incidental expenses on this account all etc. as directed by the Engineer-in-charge. (The payment will be based on the number of hours worked at the site.)				
39.	12	Providing and operating the Tipper for transporting the Earth etc., excluding loading including transportation to and from the site of operation fuel charges and any other incidental expenses on this account all etc. as directed by the Engineer-in-charge. (The payment will be based on the number of hours worked at the site and working of tipper not less than 7 hours shall be consider as one day) capacity 7.5 cum	APDSS	Day	7104.92	85259
40.	50	Fixing of column / wall claddings with 4mm thick Aluminum Composite Panel around the column / dead wall at all heights. The rate shall inclusive of tools, scaffolding, cost of weather sealant, gasket, foam, fixtures of all machineries exceptaluminium frame and all taxes etc., to be carried out by specialized agency approved by the Engineer-in-charge. (Excluding Aluminum Composite Panel).	APDSS	Sqm	1514.43	75722
41.	10	Dismantling and removing of toughen glass partition along with removal of toughen glass doors, floor springs etc., after debolting the SS bolts and nuts, SS hold fastener etc., without damaging the dismantled glass materials all as per the direction of Engineer-In-Charge.	APDSS	Sqm	195.83	1958
42.	0	Providing and fixing 12mm thick plywood complete with necessary screws etc., complete as per the direction of Engineer-In-Charge. 12mm thick	APDSS	Sq m	1401.65	0
43.	0	Providing and fixing 18mm wide PVC beading (flat) over wall lining as per the direction of Engineer-in-charge.	APDSS	meter	57.32	0
44.	10	Supply and Applying of Silicone sealant (280 ml) for filling of Glazing partitions, ACP partitions and cutting joints wherever required as directed by the Engineer-in-charge.	APDSS	No	438.98	4390
45.	0	Supplying of approved make of micro concrete for Runway / Apron / Taxi way concrete surface patches all complete as per the direction of Engineer-in-charge.	APDSS	Kg	47.37	0
46.	0	Supplying of Sika or approved make of SBR Latex Polymer compound Power material for Runway / Apron / Taxi way	APDSS	Liter	350.51	0

		concrete surface patches all complete as per the direction of Engineer-in-charge.				
47.	20	Providing and supplying sand and filling in Existing bags, keeping at site including transportation etc., complete as per the direction of Engineer-in-charge.	APDSS	Bag	68.82	1376
48.	0	Dismantling of Brick / Concrete work and making opening of required size with BOSCH 11 Kg demolition hammer which should not transfer any impact to the existing building to avoid any development of crack etc., as per direction of Engineer-in-Charge. (Payment shall be made based on the no's of Hours work at the site).	APDSS	Hour	616.65	0
49.	0	Laying available / dismantled vitrified floor tiles in different sizes (thickness to be specified by manufacturer) , laid on 20mm thick cement mortar 1: 4 (1 Cement : 4 Coarse sand) including grouting the joints with white cement and matching pigment etc., complete.(Excluding cost of tiles) a) Size of tile 60 x 60 cm.	APDSS	Sqm	505.87	0
50.	20	Fixing of available aluminum materials for doors, windows, ventilators and partitions with extruded section / appropriate Z sections and other sections, fixed with raw plugs and screws or with fixing clips or with expansion hold fasteners including necessary filling up to gaps at junctions, at top, bottom and sides with required PVC / neoprene felt etc., Aluminum snap beading for glazing / paneling, CP brass / stainless steel screws all complete as per the direction of Engineer-in-charge.(Glazing / paneling to be paid separately). a) For fixed portion.	APDSS	Sqm	734.18	14684
51.	10	Supplying and fixing of Rose Mortise handle & lock set complete in all respect as per the direction of Engineer-in- charge.	APDSS	NO	6268.91	62689
52.	15	Providing and fixing CP brass Health faucet of Jaguar make or equivalent all complete as per the direction of Engineer-In-Charge. The rate includes VAT etc.,	APDSS	No	1612.46	24187
53.	50	Providing and filling of gaps including filling of lateral joints after removing of existing filling material from the joints cleaning and applying with approved make of Polysulphide sealant including labour Charges as approved by Engineer- In-Charge.	APDSS	meter	378.93	18947
54.	0	Dismantling of Aluminum Composite Panel including disposal of unserviceable, Stacking of surplus materials at AAI store as directed by the Engineer-In-Charge.	APDSS	Sqm	781.51	0

55.	20000	Letter writing with synthetic enamel paint of approved brand & made with necessary arrangement in required languages as per approved pattern as per direction & completion satisfaction of Engineer-in-charge.	APDSS	letter per cm height	4.12	82400
56.	10	Providing and fixing of Brass Ball valve of ZOLOTO make of approved quality as directed by Engineer in charge. 25mm nominal bore	APDSS	No	660.70	6607
57.	10	Providing and fixing of Brass Ball valve of ZOLOTO make of approved quality as directed by Engineer in charge. 50mm dia Nominal Bore	APDSS	No	2869	28690
58.	15	Providing and fixing Toilet Roll Holder with Flap of Code No.AKP-35753P of approved make Jaguar or equivalent including Bolts, Nuts, Screws etc., complete in all respect as per the direction of Engineer-in-charge.	APDSS	No	899.96	13499
59.	10	Providing and fixing Automatic Soap Dispenser of approved make Jaguar or equivalent including Bolts, Nuts, Screws etc., complete in all respect as per the direction of Engineer-in-charge.	APDSS	No	3357.08	33571
60.	100	Providing Un-skilled workers for temporary nature of works/works unsusceptible to measure as and when required including necessary T&P as directed by Engineer- in-Charge. (Percentage quoted by contractor will not be added/deducted for payment)	APDSS	Day	480	48000
61.	100	Providing semi skilled / Mate workers for temporary nature of works/works unsusceptible to measure as and when required including necessary T&P as directed by Engineer- in-Charge. (Percentage quoted by contractor will not be added/deducted for payment)	APDSS	Day	500	50000
62.	100	Providing skilled workers for temporary nature of works/works unsusceptible to measure as and when required including necessary T&P as directed by Engineer-in-Charge.	APDSS	Day	550	55000
63.	0	Providing & Fixing PVC flooring sheet of plain / wood grain in gloss / matt / sue do finish with high density protective surface layer and reverse side of adhesive bonding quality conforming to IS : 2046 Type S, including cost of adhesive of approved quality as per the direction of Engineer-In-charge a) 1.5 mm thick	APDSS	Sqm	706.58	0
64.	0	Providing and fixing 3 mm thick PVC/acrylic sheet 45 including vinyl sticker	APDSS	Sqm	953024	0

		cutting and pasting complete in all respects as per the direction of Engineer-in-charge.				
65.	0	Providing and fixing vinyl opaque sticker of 25 microns of LG/MACAL/oracle or equivalent make on existing window/door glass/partition glass etc in required pattern etc complete as directed by the Engineer in charge	APDSS	Sqm	781.61	0
66.	0	Providing and fixing Acrylic sheet of white or any other colour on existing board as per requirement. 2mm thick	APDSS	Sqm	1411.10	0
67.	0	Providing and fixing Acrylic sheet of white or any other colour on existing board as per requirement. 4mmthick	APDSS	Sqm	1481.44	0
68.	0	Providing and fixing Acrylic sheet of white or any other colour on existing board as per requirement. 12mm thick	APDSS	Sqm	3513.44	0
69.	100	Providing and fixing sun control Gareware Polyester film on glass after thorough cleaning of existing surface. The rate includes removal of existing sun control film wherever required. a) Non - Reflective type	APDSS	Sqm	1153.07	115307
70.	0	Providing and fixing Edging (3M) fi m on glass after thorough cleaning of existing surface. The rate inclusive of removal of existing film wherever required etc., complete in all respects as per the direction of Engineer-In Charge	APDSS	Sqm	2415.67	0
71.	0	Providing and fixing 3M Yellow Sticker/film on floor after thorough cleaning of existing surface. The rate inclusive of removal of existing film wherever required etc., complete in all respects as per the direction of Engineer-In Charge.	APDSS	Sqm	2894.07	0
72.	30	Providing and fixing emblem/signage's/Radium stickering over glass panes/acrylic sheets including lettering as required. Overall area of the board/signage will be measured for payment i.e. maximum height maximum width. below 0.35 sqm	APDSS	Each	130.26	3908
73.	15	Providing and fixing emblem/signage's/Radium stickering over glass panes/acrylic sheets including lettering as required. Overall area of the board/signage will be measured for	APDSS	Each	947.32	14210

		payment i.e. maximum height maximum width. above 0.35 sqm and below 1.00 sqm				
74.	25	Providing and fixing emblem/signage's/ Radium sticking over glass panes/acrylic sheets including lettering of as required. Overall area of the board/ signage will be measured for payment i.e. maximum height x maximum width (a) Above 1 Sqm	APDSS	Sqm	2605.14	65129
75.	36	Deploying the man power (2 No's plumber and one Sewer man on all days) with necessary tools and takes for carrying out routine inspection preventive/corrective maintenance , attending day to day complaints with required tools, etc like repair of tap leakages, block removal of wash basin/sink/gully traps/manholes/storm water drain/rain water pipes, and any other small petty/urgent works as directed by Engineer-in charge (maintaining of plumbing and sanitary fixers in Terminal buildings)	APDSS	Month	18746	674856
76.	10	Supply, installation of Double insulated glass 35.53mm thick (Outer 6mm clear Tempered Heat Soaked Glass+1.52mm Clear PVB+6mm Excel Clear Pearl Tempered Heat Soaked Glass+ 16mm Airgap+8mm Clear Tempered Heat Soaked Glass all complete as per the direction of Engineer -In _Charge. The Transportation charges will be paid as per the submission of Bills. (Scaffolding will be paid extra)	APDSS	Sqm	11841.54	118415
77.	10	Supply, installation of 17.52mm Laminated Glass (8mm Edge Nature Clear Toughened Heat Soaked +1.52mm PVB+8mm Clear Toughened Heat Soaked Glass all complete as per the direction of Engineer -In _Charge. The Transportation charges will be paid as per the submission of Bills. (Scaffolding will be paid extra)	APDSS	Sqm	4736.61	47366
78.	0	Supply, installation of 10mm Clear Toughened Heat Soaked Glass for Automatic Sliding Door Transportation charges will be paid as per the submission of Bills. (Scaffolding will be paid extra)	APDSS	Sqm	2013.06	0
79.	0	Providing and placing glass of 5mm thick with machine finished edges for tables	APDSS	Sqm	1282.39	0
80.	0	Providing and fixing 6mm thick PVC pipe and all other necessary fittings including labour charges as directed by Engineer-in-	APDSS	meter	225.23	0

		Charge. 100mm				
81.	0	Providing and fixing 6mm thick PVC pipe and all other necessary fittings including labour charges as directed by Engineer-in-Charge. 150mm	APDSS	meter	330.45	0
82.	0	Providing Bitumen Felt sheet on roof sheet including fixing all complete as per the Direction of Engineer-In-Charge.	APDSS	Sqm	1128.37	0
83.	0	Providing and Fixing PVC mesh of required width in minimum size 10X10 mm made of G1 wire of required size over PVC coating including strengthening as required complete all i/c fixing as per the direction of EIC.	APDSS	Sqm	61.98	0
84.	5	Providing and fixing double action hydraulic floor spring having brand logo embossed on the body / plate with double spring mechanism and door weight up to 125 kg, or doors, including cost of cutting floors, embedding in floors as required and making good the same matching to the existing floor finishing and cover plates with brass pivot and single piece M.S. sheet outer box with slide plate etc. complete as per the direction of Engineer-in-charge	APDSS	No	10717.78	53589
85.	10	Providing and fixing Patch Lock for Glass door make of ozone including necessary fittings etc all complete as per direction of the EIC	APDSS	No	2458.30	24583
86.	200	Painting structural steel, railing, canopy etc., with polyurethane paint prepared and applied as per manufacturers specifications including cleaning the existing surface thoroughly, all scaffolding , safety measures , tools and plants etc (old work(one or more coats)) complete as per the direction of Engineer-in- charge	APDSS	Sqm	187.01	37402
87.	5	Supply and fixing of Koehler make EWC spare parts all complete as per the direction of EIC Gasket tank outlet Of code 1169507	APDSS	No	112.49	562
88.	5	Supply and fixing of Koehler make EWC spare parts all complete as per the direction of EIC Bowl inlet pipe of code 1290889	APDSS	No	201.31	1007
89.	5	Supply and fixing of Koehler make EWC spare parts all complete as per the direction of EIC	APDSS	No	497.34	2487

		Connector Accessory pack of code 1046327				
90.	5	Supply and fixing of Koehler make EWC spare parts all complete as per the direction of EIC Bevel in wall tank face plate PC	APDSS	No	2575.53	12878
91.	5	Supply and fixing of automatic soap dispensers spares in NTB as per direction of Engineer-in-charge Washers set ES0807	APDSS	No	47.37	237
92.	5	Supply and fixing of automatic soap dispensers spares in NTB as per direction of Engineer-in-charge Control box complete ES0802	APDSS	No	2711.71	13559
93.	5	Supply and fixing of automatic soap dispensers spares in NTB as per direction of Engineer-in-charge PCB ES0805	APDSS	No	1006.53	5033
94.	5	Supply and fixing of automatic soap dispensers spares in NTB as per direction of Engineer-in-charge Ball ES0808	APDSS	No	17.76	89
95.	5	Supply and fixing of automatic soap dispensers spares in NTB as per direction of Engineer-in-charge Control Box Empty ESO801	APDSS	No	888.12	4441
96.	0	Providing and fixing beveled edge mirror of superior glass (of approved quality and of required size as directed by engineer in charge) complete with C.P. brass screws and washers complete.	APDSS	Sqm	2419.38	0
97.	2	Repairing/realignment of aluminium sliding doors including replacing with new sliding wheel arrangement and all necessary fittings to sliding doors as per the direction of Engineer-in-charge.	APDSS	No	3197.22	6394
98.	10	Providing and fixing spare parts for the EWC make of Kohler including all extra fitting items as directed by Engineer-in-charge. Flow Control Valve Assembly , Product Code: 1203558	APDSS	No	264.07	2641
99.	10	Providing and fixing spare parts for the EWC make of Kohler including all extra fitting items as directed by Engineer-in-charge. Hose Assembly, Product Code: 1204697	APDSS	No	1076.40	10764

100	10	Providing and fixing spare parts for the EWC make of Kohler including all extra fitting items as directed by Engineer-in-charge. Cleaning Assembly, Product Code: 1203574	APDSS	No	255.78	2558
101	10	Providing and fixing spare parts for the EWC make of Kohler including all extra fitting items as directed by Engineer-in-charge. Accessory pack, Product Code: 1217696-0	APDSS	No	401.43	4014
102	10	Providing and fixing spare parts for the EWC make of Kohler including all extra fitting items as directed by Engineer-in-charge. Hinge Assembly Right, Product Code: 1171470-0	APDSS	No	1064.55	10646
103	10	Providing and fixing spare parts for the EWC make of Kohler including all extra fitting items as directed by Engineer-in-charge. Hinge Assembly Left, Product Code: 1171469-0	APDSS	No	1064.55	10646
104	10	Providing and fixing spare parts for the EWC make of Kohler including all extra fitting items as directed by Engineer-in-charge. Hard pack, Product Code: 1141995	APDSS	No	292.49	2925
105	10	Providing and fixing spare parts for the EWC make of Kohler including all extra fitting items as directed by Engineer-in-charge. INLET+ SCREW Assembly, Product Code: 1204698	APDSS	No	239.20	2392
106	0	Manufacturing, supplying and fixing retro reflective sign boards face to be fully covered with high intensity encapsulated type heat activated retro reflective sheeting Backside of sheet to be painted with two or more coats of epoxy paint over and including appropriate priming coat including all leads and lifts etc. complete as per drawing , specification and direction of Engineer-in-charge	APDSS	sqm	2149.16	0
107	150	Repairing and fixing false ceiling at all height including providing and fixing of frame work made of special sections, power pressed from M.S. sheets and	APDSS	Sqm	1452.07	217811

		galvanized with zinc coating of 120 gms/sqm including removal of existing false ceiling and labour charges				
108	30	Deploying the man power (1 No welder) with necessary welding tools and welding rods as decided by Engineer-in-charge.	APDSS	Job	2564.88	76946
109	0	Repairing of pot holes by preparing the existing surface of concrete floor by scarification and cleaning by wire brushing etc. to remove all foreign contaminants, loosely adhered cementitious layer, oil etc. to expose clean sound base concrete substrate. Providing and Applying two component, epoxy resin based primer, Dr. Fixit PU Primer on the prepared surface, which has pull off adhesion strength of more than 2 mpa.	APDSS	kg	888.12	0
110	0	Providing and laying of epoxy screed (of Approved Make) after the application of Moisture Insensitive Primer, and "sand mortar, one part by weight of resin formulation mixed with fixed parts of sand, with suitable primer. 1 Part By Weight of Epoxy: 4 to 7 Parts of hand as per Manufacturers Specification. Complete as per direction of Engineer-in-Charge	APDSS	kg	298.81	0
111	0	Providing and applying Backer rod with desired thickness according to the joints and applying bond breaker tape on top of the backer rod.	APDSS	kg	4.55	0
112	0	Providing and sealing of construction, dummy and expansion joints in concrete pavement with fresh Polysulphide sealant of reputed manufacturer confirming to BS 5212-1990 or IS : 11433-1995, including providing temporary strip of adequate size during resurfacing treatment for maintaining the joints, rounding of edges including providing and applying Sealant primer two coats compatible with the brand of Polysulphide and preparing the surface and applying masking tape along the edges of joints to prevent accidents spillage of sealant on top surface and to give neat finish to the sealant and removing the masking tape after application of sealant etc. complete as per direction of Engineer-in-Charge	APDSS	kg	8.10	0
113	5	supplying and fixing of Toughened glass door locks of approved makes as directed by Engineer in charge	APDSS	No	3732.50	18663
114	0	Fixing of C.I Man hole cover of various sizes including demolishing of existing R.C.C. work manually/ by mechanical	APDSS	kg	110.47	0

		means and stacking of useful materials near the site and disposal of unserviceable materials within 50 meters lead as per direction of Engineer-in-charge				
115	0	Supply and Applying Polyurethane PU foam spray (360ml) as and when necessary as directed by Engineer -in - charge	APDSS	No	865.62	0
116	0	Supply and Applying of rust lick 631 rust lubricant spray (370 ml) as and when necessary as directed by Engineer - in - charge	APDSS	No	439.32	0
117	0	Supply of Stainless steel studs 35mm dia x 25mm dia x 4.5mm thick ness suitable for positional tiles (36 per square feet) material SS 304, with stem.	APDSS	No	127.89	0
118	0	Supply of Stainless steel stripes 280mm dia x 35mm dia x 4.5mm thickness suitable for linear directional tiles material SS 304. With stem.	APDSS	No	402.61	0
119	5	Providing and fixing aluminium die cast body tubular type universal hydraulic door closer (having brand logo with ISI, IS : 3564, embossed on the body, with necessary accessories and screws etc. complete.	APDSS	No	1743.70	8719
						8167245

The Estimate Contract Value Rs 81,67,245(Eighty One Lakhs Sixty Seven Thousand Two Hundred and Forty Five Rupees only)